# PRELIMINARY PLAN APPLICATION - MAJOR LAND DEVELOPMENT PROJECT

FOR
10,640 SQ. FT. RETAIL BUILDING,
Parcel ID# 114-012 LOT A
BRONCOS HIGHWAY (RT. #102)
BURRILLVILLE, RHODE ISLAND


DATE: DECEMBER 28, 2023

#### **OWNER**

NASON SQUARE LLC 28 RIDGE HILL ROAD NORTH SMITHFIELD, RI 02896

#### **APPLICANT & DEVELOPER**


REBEL-UNION PARTNERS, LLC
93 NORTH MAIN STREET
WEST HARTFORD, CT 06107
ATTENTION: MARK D'ADDABBO
PHONE NUMBER: 860-729-6812



NOT TO SCALE

#### **SHEET INDEX**


SHEET II	SHEEL INDEX		
SHEET #	DRAWING TITLE		
1	EXISTING CONDITIONS PLAN		
2	ZONING IMPROVEMENT LOCATION SURVEY - PROPOSED		
3	SITE GRADING & DRAIANGE PLAN		
4	SITE UTILITIES PLAN		
5	EROSION & SEDIMENT CONTROL PLAN		
6	GENERAL SITE NOTES		
7	EROSION AND SEDIMENT CONTROL NOTES & DETAILS		
8	STORMWATER BASIN DETAIL PLAN		
9	SANITARY SEWER LATERAL PLAN & PROFILE		
10 -15	MISCELLANEOUS SITE DETAILS		
LS-1	LANDSCAPING PLAN		
PH-1.0	SITE LIGHTING PLAN		








630 MAIN STREET, UNIT #1A
CROMWELL, CONNECTICUT 06416
PHONE: (860)-529-6812, FAX: (860)-721-7709


1	03/02/34	PER PEER REVIEW AND PLANNER COMMENTS	J.P.C.
NO.	DATE	DESCRIPTION	BY














#### SITE PLAN NOTES

- ALL CONSTRUCTION SHALL COMPLY WITH TOWN OF BURRILLVILLE, STATE OF RHODE ISLAND DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS IN THE ABOVE REFERENCED HIERARCHY. IF SPECIFICATIONS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS.
- . THE OWNER IS RESPONSIBLE FOR OBTAINING ALL NECESSARY ZONING PERMITS REQUIRED BY GOVERNMENT AGENCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ALL TOWN CONSTRUCTION PERMITS, INCLUDING DOT PERMITS AND SEWER AND WATER CONNECTION PERMITS. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.
- . REFER TO OTHER PLANS, DETAILS AND NOTES FOR ADDITIONAL INFORMATION. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE SITE ENGINEER IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND FOR FIELD CONDITIONS SO THAT APPROPRIATE REVISIONS CAN BE MADE PRIOR TO BIDDING. ANY CONFLICT BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE CONFORMED WITH THE LOCAL CONSTRUCTION MANAGER PRIOR TO BIDDING.
- . THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL PRODUCTS, MATERIALS AND PLAN SPECIFICATIONS TO THE OWNER AND SITE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY TO THE SITE. ALLOW A MINIMUM OF 14 WORKING DAYS FOR REVIEW.
- 5. THE CONTRACTOR SHALL FOLLOW THE SEQUENCE OF CONSTRUCTION NOTES PROVIDED ON THE EROSION CONTROL PLAN.
- 5. THE CONTRACTOR SHALL REFERENCE ARCHITECTURAL PLANS FOR EXACT DIMENSIONS AND CONSTRUCTION DETAILS OF BUILDING, OUTSIDE DISPLAY AREA, AND THE RAISED CONCRETE SIDEWALKS AND RAMPS.
- SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE ENGINEER IMMEDIATELY FOR DIRECTIONS REFORE PROCEEDING FURTHER WITH WORK IN THIS AREA
- 3. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER AND THE LOCAL MUNICIPALITIES. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY SERVICE HAS BEEN
- 9. ALL SITE DIMENSIONS ARE REFERENCED TO THE FACE OF CURBS OR EDGE OR PAVING UNLESS OTHERWISE NOTED. ALL BUILDING DIMENSIONS ARE REFERENCED TO THE OUTSIDE FACE OF THE STRUCTURE.
- . THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS, FENCES, TRAFFIC CONTROLLERS AND UNIFORMED TRAFFIC OFFICERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE LOCAL GOVERNING AUTHORITIES.
- 1 REFER TO DETAIL SHEETS FOR PAVEMENT CURRING AND SIDEWALK INFORMATION

. TRAFFIC CONTROL SIGNAGE SHALL CONFORM TO THE STATE DOT STANDARD DETAIL SHEETS AND THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. SIGNS SHALL BE

- INSTALLED PLUMB WITH THE EDGE OF THE SIGN 2' OFF THE FACE OF THE CURB, AND WITH 7' VERTICAL CLEARANCE UNLESS OTHERWISE DETAILED OR NOTED. . THE CONTRACTOR SHALL ABIDE BY ALL OSHA FEDERAL STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS. ANY UTILITY COMPANY FEES SHALL BE PAID FOR BY THE CONTRACTOR.
- 14. THE CONTRACTOR SHALL SUBMIT A SHOP DRAWING OF THE PAINT MIXTURE PRIOR TO STRIPING.
- PAVEMENT MARKING KEY:
- 4' SOLID YELLOW DOUBLE LINE
- 4' SOLID YELLOW LINE 4" SYL 4"SWL 4" SOLID WHITE LINE
- 12" SOLID WHITE STOP BAR
- 4" BROKEN WHITE LINE 10' STRIPE 30' SPACE
- 3. PARKING SPACES SHALL BE STRIPED WITH 4" SWL; HATCHED AREA SHALL BE STRIPED WITH 4' SWL AT A 45° ANGLE, 2' ON CENTER. HATCHING SYMBOLS, AND STRIPING FOR HANDICAPPED SPACES SHALL BE PAINTED BLUE. OTHER MARKINGS SHALL BE PAINTED WHITE OR AS NOTED.
- 7. THE CONTRACTOR SHALL RESTORE ANY DRAINAGE STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS OR SIGNAGE DISTURBED DURING CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AS APPROVED BY THE ENGINEER.
- 8. THE CONTRACTOR SHALL PROVIDE AS—BUILT RECORDS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER AT THE END OF CONSTRUCTION.
- 9. THE ARCHITECT OR ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ARCHITECT AND ENGINEER HAVE NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.
- 20. THE CONTRACTOR SHALL COMPLY WITH CFR 29 PART 1926 FOR EXCAVATION TRENCHING AND TRENCH PROTECTION REQUIREMENTS..
- 1. ALTERNATIVE METHODS AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED IF REVIEWED AND APPROVED BY THE OWNER, SITE ENGINEER, AND APPROPRIATE REGULATORY AGENCY PRIOR TO INSTALLATION DURING THE BIDDING PROCESS.
- 2. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION. THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" 72 HOURS BEFORE COMMENCEMENT OF WORK AT
- 23. PAVEMENT MARKINGS SHALL BE HOT APPLIED TYPE IN ACCORDANCE WITH CT DOT SPECIFICATIONS, UNLESS WHERE EPOXY RESIGN PAVEMENT MARKINGS ARE INDICATED.
- 24. RI DOT ENCROACHMENT PERMIT SHALL BE OBTAINED BY CONTRACTOR WHO SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC PROTECTION NECESSARY FOR THE WORK.
- 5. AN EROSION CONTROL BOND IS REQUIRED TO BE POSTED BY THE CONTRACTOR BEFORE THE START OF ANY ACTIVITY ON OR OFF SITE.
- 26. THESE PLANS ARE FOR PERMITTING PURPOSES ONLY AND ARE NOT FOR CONSTRUCTION. NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.
- 28. THESE PLANS ARE FOR PERMITTING.
- 29. THE SITE IS PROPOSED TO BE SERVICED BY WELL AND PUBLIC SEWER SYSTEM.
- 30. PROPERTY SHOWN ON F.I.R.M. NO. 44007C0151G. DATED: MARCH 2, 2009. THE PORTION OF THIS PROPORTY THAT IS BEING DEVELOPED IS IN A FLOOD ZONE "X".

"1(800)922-4455" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS.

- 1. 12" SWSB (STOP BAR) AND 4" SYDL AND SWL PAVEMENT MARKINGS LOCATED IN DRIVEWAYS AND IN STATE HIGHWAY SHALL BE EPOXY RESIN TYPE ACCORDING TO CT DOT
- 32. FIRE LANES SHALL BE ESTABLISHED AND PROPERLY DESIGNATED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN FIRE MARSHAL.
- 33. THE APPLICANT WILL PROVIDE AND MAINTAIN ADEQUATE SIGHT DISTANCES AT ALL DRIVEWAY INTERSECTIONS. CURRENT STATE OF RHODE ISLAND HIGHWAY DESIGN
- STANDARDS WILL APPLY TO REQUIRED SIGHT DISTANCES. 34. THE APPLICANT WILL REGISTER BUILDING ALARMS PER TOWN ORDINANCE.
- 35. THE APPLICANT WILL CONTROL DUST AND DEBRIS ON THE SURROUNDING ROADWAYS DURING CONSTRUCTION. PROPER SAFETY PRECAUTIONS AND EQUIPMENT ARE TO BE UTILIZED WHEN WORKING ON PUBLIC ROADWAYS AND ARE THE APPLICANT'S RESPONSIBILITY TO PROVIDE.
- 36. THE APPLICANT WILL OBTAIN A RHODE ISLAND DEPARTMENT OF TRANSPORTATION ENCROACHMENT PERMIT FOR ANY WORK DONE IN THE STATE RIGHT OF WAY.
- 37. THE APPLICANT MUST COMPLY WITH RHODE ISLAND DEPARTMENT OF TRANSPORTATION STIPULATIONS/REGULATIONS WHEN APPLICABLE.
- 38. ALL DISTURBED PAVEMENT MARKINGS MUST BE REPLACED WITH EPOXY PAINT.

#### GRADING AND DRAINAGE NOTES

#### GRADING GENERAL NOTES:

- 1. SEE THIS PLAN SHEET FOR ADDITIONAL SITE PLAN AND GENERAL NOTES.
- 2. THE GRADING AND DRAINAGE PLAN IS INTENDED TO DESCRIBE GRADING AND DRAINAGE ONLY. REFER TO SITE PLAN FOR GENERAL INFORMATION, AND DETAIL SHEETS FOR DETAILS. SEE MEP DRAWINGS FOR BUILDING CONNECTION LOCATIONS AND DETAILS.
- 3. THE CONTRACTOR SHALL PRESERVE EXISTING VEGETATION WHERE POSSIBLE AND/OR AS NOTED ON DRAWINGS. REFER TO EROSION CONTROL PLAN FOR LIMIT OF DISTURBANCE AND NOTES.
- 4. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING.
- 5. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS REQUIRED BY GOVERNMENT AND LOCAL AGENCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FROM THE LOCAL MUNICIPALITIES REQUIRED TO PERFORM ALL REQUIRED WORK, INCLUDING FOR STREET CUTS AND CONNECTIONS TO EXISTING UTILITIES. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.
- 6. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS FENCES AND UNIFORMED TRAFFIC CONTROLLERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE STATE AND LOCAL GOVERNING AUTHORITIES.
- 7. THE CONTRACTOR SHALL COMPACT FILL IN 12" MAXIMUM LIFTS UNDER ALL PARKING, BUILDING, AND DRIVE AREAS TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D1557 (MODIFIED PROCTOR TEST), OR AS DIRECTED BY THE GEOTECHNICAL ENGINEER.
- 8. UNDERDRAINS SHALL BE ADDED, IF DETERMINED NECESSARY IN THE FIELD BY THE DESIGN OR TOWN ENGINEER AFTER SUBGRADE IS ROUGH GRADED, AS APPROVED BY THE BURRILLVILLE TOWN STAFF. 9. VERTICAL DATUM IS NAVD 1988.
- 10. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE TOWN OF BURRILLVILLE AGENT PRIOR TO THE START OF WORK ON THE SITE.
- 11. PROPER CONSTRUCTION PROCEDURES SHALL BE FOLLOWED ON ALL IMPROVEMENTS WITHIN THIS PARCEL SO AS TO PREVENT THE SILTING OF ANY WATERCOURSE OR WETLANDS IN ACCORDANCE WITH THE REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION GUIDELINES FOR SOIL EROSION AND SEDIMENT POLLUTION CONTROL. IN ADDITION, THE CONTRACTOR SHALL STRICTLY ADHERE TO THE "EROSION CONTROL PLAN" CONTAINED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE TO POST ALL BONDS AS REQUIRED BY THE LOCAL MUNICIPALITIES, OR SOIL CONSERVATION SERVICE WHICH WOULD GUARANTEE THE PROPER IMPLEMENTATION OF THE PLAN.
- 12. ALL SITE WORK, MATERIALS OR CONSTRUCTION, AND CONSTRUCTION METHODS FOR EARTHWORK STORM DRAINAGE AND UTILITY WORK SHALL CONFORM TO THE SPECIFICATIONS AND DETAILS AND APPLICABLE SECTIONS OF THE STATE OF RHODE ISLAND DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE STATED IN THE PROJECT MANUAL SPECIFICATIONS. ALL FILL MATERIALS UNDER STRUCTURES AND PAVED AREAS SHALL BE PER THE SPECIFICATIONS, AND/OR PROJECT GEOTECHNICAL REPORT, AND SHALL BE PLACED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE DOT, UNDER THE SUPERVISION OF A QUALIFIED PROFESSIONAL ENGINEER. MATERIAL SHALL BE COMPACTED IN 12" LIFTS TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D 1557 AT 3 +/- PERCENT OF OPTIMUM MOISTURE CONTENT.
- 13. ALL DISTURBANCE INCURRED TO TOWN OR STATE PROPERTY DUE TO CONSTRUCTION SHALL BE RESTORED TO ITS PREVIOUS CONDITION OR BETTER, TO THE SATISFACTION OF THE TOWN OF BURRILLVILLE AUTHORITY AND STATE OF RHODE ISLAND.
- 14. ALL CONSTRUCTION SHALL COMPLY WITH THE LOCAL MUNICIPALITY'S STANDARDS AND STATE OF RHODE ISLAND'S DOT SPECIFICATIONS. ALL CONSTRUCTION WITHIN A DOT RIGHT OF WAY SHALL COMPLY WITH ALL DEPARTMENT OF TRANSPORTATION STANDARDS. WHERE SPECIFICATIONS OR STANDARDS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION OR STANDARD SHALL BE SUPERIOR. PRODUCT NOTES:
- 1. SHOP DRAWINGS: THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF MATERIALS AND STRUCTURES FOR REVIEW AND APPROVAL PRIOR TO DELIVERY TO THE SITE. ALLOW 14 WORKING DAYS FOR REVIEW.
- 2. POLY VINYL CHLORIDE PIPE (PVCP) FOR STORM AND SANITARY PIPING SHALL HAVE BUILT-IN RUBBER GASKET JOINTS. PVCP SHALL CONFORM TO ASTM D-3034 (SDR35) WITH COMPRESSION JOINTS AND MOLDED FITTINGS. PVCP SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS; ASTM-D2321 AND MANUFACTURERS RECOMMENDED PROCEDURE.
- 3. ALL RCP SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-76; ALL RCP SHALL BE CLASS IV UNLESS OTHERWISE SHOWN. JOINTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-443.
- 4. MANHOLE SECTIONS AND CONSTRUCTION SHALL CONFORM TO ASTM C-478.
- 5. HIGH DENSITY POLYETHYLENE (HDPE) STORM SEWER 12" OR GREATER IN DIAMETER SHALL BE HI-Q SURE-LOK 10.8 PIPE AS MANUFACTURED BY HANCOR INC. OR APPROVED EQUAL. HDPE PIPE SHALL HAVE SMOOTH INTERIOR AND CORRUGATED EXTERIOR AND SHALL MEET THE REQUIREMENTS OF ASSHTO M294, TYPE PIPE SECTIONS SHALL BE JOINED WITH BELL-AND-SPIGOT JOINT MEETING THE REQUIREMENTS OF AASHTOS. M294. THE BELL SHALL BE AN INTEGRAL PART OF THE PIPE AND PROVIDE A MINIMUM PULL-APART STRENGTH OF 400 POUNDS. THE JOINT SHALL BE WATERTIGHT ACCORDING TO THE REQUIREMENTS OF ASTM D3212. GASKETS SHALL BE MADE OF POLYISOPRENE MEETING THE REQUIREMENTS OF ASTM F477. ALTERNATIVE HDPE PIPE MAY BE USED IF APPROVED BY THE ENGINEER AND CONSTRUCTION MANAGER PRIOR
- 6. HIGH DENSITY POLYETHYLENE (HDPE) STORM SEWER LESS THAN 12" IN DIAMETER SHALL BE HI-Q PIPE AS MANUFACTURED BY HANCOR INC. OR APPROVED EQUAL. HDPE PIPE SHALL HAVE SMOOTH INTERIOR ANI CORRUGATED EXTERIOR AND SHALL MEET THE REQUIREMENTS OF AASHTO 252, TYPE S. PIPE SECTIONS SHALL BE JOINED WITH COUPLING BANDS OR EXTERNAL SNAP COUPLERS COVERING AT LEAST 2 FULL CORRUGATIONS ON EACH END OF THE PIPE. SILT-TIGHT (GASKET) CONNECTIONS SHALL INCORPORATE A CLOSED SYNTHETIC EXPANDED RUBBER GASKET. MEETING THE REQUIREMENTS OF AASHTO D1056 GRADE 2A2. GASKETS SHALL BE INSTALLED ON THE CONNECTION BY THE PIPE MANUFACTURER. ALTERNATIVE HDPE PIPE MAY BE USED IF APPROVED BY THE ENGINEER AND CONSTRUCTION MANAGER PRIOR TO ORDERING.

#### GENERAL NOTES

- 1. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE SITE ENGINEER AND ARCHITECT IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS.
- 2. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER AND THE LOCAL MUNICIPALITIES. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY SERVICE HAS BEEN PROVIDED.
- 3. THE CONTRACTOR SHALL ABIDE BY ALL OSHA FEDERAL STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS. ANY UTILITY COMPANY FEES SHALL BE PAID FOR BY THE CONTRACTOR.
- 4. THE CONTRACTOR SHALL PROVIDE RECORD DRAWINGS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER AT THE END OF CONSTRUCTION.
- 5. THE ARCHITECT OR ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ARCHITECT AND ENGINEER HAVE NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.
- 6. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUA LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" 72 HOURS BEFORE COMMENCEMENT OF WORK AT "811" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS.
- 7. DO NOT SCALE DRAWINGS. DIMENSIONS GOVERN OVER SCALED DIMENSIONS.
- 8. IF PLANS AND OR SPECIFICATIONS ARE IN CONFLICT, THE MOST EFFECTIVE SHALL APPLY AS DETERMINED BY A LICENSED PROFESSIONAL AND APPROVED BY TOWN STAFF
- 9. ALL CONTRACTORS AND SUBCONTRACTORS SHALL OBTAIN COMPLETE DRAWING PLAN SETS FOR BIDDING AND CONSTRUCTION. PLAN SETS SHALL NOT BE DISASSEMBLED INTO PARTIAL PLAN SETS FOR USE BY CONTRACTORS AND SUBCONTRACTORS OF INDIVIDUAL TRADES. IT SHALL BE THE CONTRACTOR'S AND SUBCONTRACTOR'S RESPONSIBILITY TO OBTAIN COMPLETE PLAN SETS FOR USE IN BIDDING AND CONSTRUCTION.
- 10. ALL NOTES AND DIMENSIONS DESIGNATED "TYPICAL" APPLY TO ALL LIKE OR SIMILAR CONDITIONS THROUGHOUT THE PROJECT.
- 11. CONTRACTOR'S TO TAKE AND VERIFY ALL DIMENSIONS AND CONDITIONS OF THE WORK AND BE RESPONSIBLE FOR COORDINATION OF SAME. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO START OF WORK.
- 12. THESE PLANS ARE FOR PERMITTING PURPOSES ONLY AND ARE NOT FOR CONSTRUCTION. NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.

#### **UTILITIES NOTES**

- UTILITY CONSTRUCTION NOTES:
- 1. CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE LOCAL MUNICIPALITIES TO SECURE PERMITS AND FOR PAYMENT OF FEES FOR STREET CUTS AND CONNECTIONS TO EXISTING UTILITIES.
- 2. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS FENCES AND UNIFORMED TRAFFIC CONTROLLERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE LOCAL GOVERNING AUTHORITIES.
- 3. THIS PLAN DETAILS SITE INSTALLED PIPES UP TO 5' FROM THE BUILDING FACE. REFER TO DRAWINGS BY OTHERS FOR BUILDING CONNECTION POINT OR AT EXISTING UTILITY OR PIPE CONNECTION POINT.
- 4. THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE SEWERS CROSS UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT THE SITE ENGINEER IN THE EVENT OF ANY DISCOVERED OR UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED UTILITIES SO THAT AN APPROPRIATE MODIFICATION
- 5. UTILITY CONNECTION DESIGN AS REFLECTED ON THE PLAN MAY CHANGE SUBJECT TO UTILITY CO. AND TOWN
- 6. THE CONTRACTOR SHALL ENSURE THAT ALL UTILITY COMPANIES AND TOWN STANDARDS FOR MATERIALS AND CONSTRUCTION METHODS ARE MET. THE CONTRACTOR SHALL PERFORM PROPER COORDINATION WITH THE RESPECTIVE UTILITY PROVIDER, TOWN OF BURRILLVILLE PUBLIC WORKS DEPARTMENT AND TOWN OF BURRILLVILLE WATER & SEWER DEPARTMENT.
- 7. THE CONTRACTOR SHALL ARRANGE FOR AND COORDINATE WITH THE RESPECTIVE UTILITY COMPANIES FOR SERVICE INSTALLATIONS AND CONNECTIONS. THE CONTRACTOR SHALL COORDINATE WORK TO BE PERFORMED BY THE VARIOUS UTILITY COMPANIES AND SHALL PAY ALL FEES FOR CONNECTIONS, DISCONNECTION, REALLOCATIONS, INSPECTIONS, AND DEMOLITION.
- 8. ALL EXISTING PAVEMENT WHERE UTILITY PIPING IS TO BE INSTALLED SHALL BE SAW CUT. AFTER UTILITY INSTALLATION IS COMPLETED THE SITE CONTRACTOR SHALL INSTALL TEMPORARY OR PERMANENT PAVEMENT REPAIR AS DETAILED ON THE PLANS OR AS REQUIRED BY THE AUTHORITY HAVING JURISDICTION.
- 9. ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER ACCURATE METHOD.
- 10. SANITARY LATERAL SHALL MAINTAIN (10' MIN. HORIZONTAL 1.5' VERTICAL MIN.) SEPARATION DISTANCE FROM WATER LINES, OR ADDITIONAL PROTECTION MEASURES WILL BE REQUIRED WHERE PERMITTED. 11. RELOCATION OF UTILITY COMPANY FACILITIES SUCH AS POLES, TO BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE FACILITY OWNERS.
- 12. THE CONTRACTOR SHALL COMPACT THE PIPE BACKFILL IN 12" LIFTS ACCORDING TO THE PIPE BEDDING DETAILS. TRENCH BOTTOM SHALL BE STABLE IN HIGH GROUNDWATER AREAS. A PIPE FOUNDATION SHALL BE USED IN AREAS OF ROCK EXCAVATION. STORM SEWERS MAY BE PLACED PRIOR TO PLACING FILL.
- 13. CONTRACTOR TO PROVIDE SLEEVES UNDER FOOTINGS FOR UTILITY CONNECTIONS.

VERIFIED WITH THE MEP DRAWINGS AND CONSTRUCTION MANAGER.

- 14. UTILITY PENETRATIONS AND LOCATIONS ARE SHOWN FOR THE CONTRACTOR'S INFORMATION AND SHALL BE
- 15. ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION FOR APPROVAL PRIOR TO BACKFILLING, IN ACCORDANCE WITH THE APPROPRIATE UTILITY COMPANY AND/OR THE LOCAL MUNICIPALITIES' REQUIREMENTS.

16. A ONE-FOOT MINIMUM CLEARANCE BETWEEN WATER, GAS, ELECTRICAL, AND TELEPHONE LINES AND STORM

SEWERS SHALL BE PROVIDED. A SIX-INCH MINIMUM CLEARANCE SHALL BE MAINTAINED BETWEEN STORM AND SANITARY SEWER WITH A CONCRETE ENCASEMENT. 17. CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS

TO BUILDING STUB OUTS, INCLUDING ROOF/FOOTING DRAIN CONNECTIONS TO ROOF LEADERS AND TO STORM

- DRAINAGE SYSTEM. 18. MANHOLE RIMS SHALL BE SET TO ELEVATIONS SHOWN. SET ALL EXISTING MANHOLE FRAMES AND VALVE
- COVERS TO BE RAISED OR LOWERED FLUSH WITH FINAL GRADE AS NECESSARY. 19. SITE CONTRACTOR SHALL COORDINATE INSTALLATION OF CONDUIT AND CABLES FOR SITE LIGHTING WITH THE
- BUILDING ELECTRICIAN/ELECTRICAL CONTRACTOR. 20. CONTRACTOR SHALL COORDINATE INSTALLATION FOR ELECTRICAL SERVICES TO PYLON SIGNS AND SITE
- LIGHTING WITH THE BUILDING ELECTRICIAL/ELECTRICAL CONTRACTOR.
- 21. THE CONTRACTOR SHALL RESTORE ANY UTILITY STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, OR LANDSCAPED AREAS DISTURBED DURING CONSTRUCTION, TO THEIR ORIGINAL CONDITION OR BETTER.
- 22. INFORMATION ON EXISTING UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES INCLUDING SERVICES. CONTACT "CALL BEFORE YOU DIG" AT 811 72 HOURS PRIOR TO CONSTRUCTION AND VERIFY ALL UNDERGROUND AN OVERHEAD UTILITY LOCATIONS.
- 23. THE CONTRACTOR SHALL ARRANGE AND COORDINATE WITH UTILITY COMPANIES AND THE TOWN OF BURRILLVILLE FOR WORK TO BE PERFORMED BY UTILITY COMPANIES OR BY THE TOWN OF BURRILLVILLE. THE CONTRACTOR SHALL PAY ALL UTILITY FEES AND REPAIR PAVEMENTS AS NECESSARY.
- 24. ELECTRIC, AND TELEPHONE SERVICES SHALL BE INSTALLED UNDERGROUND FROM SERVICE POLE CL&P #1543. THE CONTRACTOR SHALL INSTALL AND BACKFILL TWO 4" PVC CONDUITS FOR TELEPHONE SERVICE. FOUI 4" PVC CONDUITS FOR ELECTRIC SERVICE PRIMARY, PVC CONDUITS FOR ELECTRICAL SECONDARY PER BUILDING ELECTRICAL PLANS (SCHEDULE 80N UNDER PAVEMENT, SCHEDULE 40 IN NON PAVEMENT AREAS). SERVICES MAY BE INSTALLED IN A COMMON TRENCH WITH 1" CLEAR SPACE BETWEEN. MINIMUM COVER IS 36" ON ELECTRIC CONDUITS, AND 24" ON TELEPHONE CONDUITS. SERVICES SHALL BE MARKED WITH MAGNETIC LOCATOR TAPE AND SHALL BE BEDDED, INSTALLED, AND BACKFILLED IN ACCORDANCE WITH ELECTRIC COMPANY, AND PHONE COMPANY STANDARDS. GALVANIZED STEEL ELECTRICAL CONDUIT SHALL BE USED AT POLE AND TRANSFORMER LOCATIONS. INSTALL HANDHOLES AS REQUIRED. INSTALL CONCRETE ENCASEMENT ON PRIMARY ELECTRIC CONDUITS IF REQUIRED BY ELECTRIC COMPANY.
- 25. ALL WATER LINES TO HAVE A MINIMUM COVER OF 54-INCHES. ALL LINES SHALL BE BEDDED IN 6" SAND
- AND BACKFILLED WITH 12" SAND. 26. ALL WATER MAINS, WATER SERVICES AND SANITARY SEWER LATERAL SHALL CONFORM TO THE DEPARTMENT OF ENVIRONMENTAL HEALTH, APPLICABLE TOWN OF BURRILLVILLE WATER & SEWER DEPARTMENT SPECIFICATIONS, AS
- WELL AS TO OTHER APPLICABLE CODES AND SPECIFICATIONS FOR POTABLE WATER SYSTEMS. 27. ALTERNATIVE METHODS AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED IF REVIEWED AND APPROVED BY THE OWNER, ENGINEER, UTILITY PROVIDER AND APPROPRIATE REGULATORY AGENCIES PRIOR TO
- 28. THE CONTRACTOR SHALL MAINTAIN ALL UTILITY CONNECTIONS TO EXISTING ABUTTING HOUSES & COMMERCIAL BUILDINGS WITHOUT INTERRUPTION UNLESS/UNTIL AUTHORIZED TO DISCONNECT BY THE OWNERS, THE PROJECT ENGINEER, UTILITY PROVIDER AND GOVERNING AUTHORITIES.
- 29. ANY EXISTING POTABLE WATER WELLS AND SEPTIC TANKS/ABSORPTION AREAS SHALL BE ABANDONED AND REMOVED PER THE DEPARTMENT OR ENVIRONMENTAL PROTECTION AND HEALTH CODE REQUIREMENTS.
- 30. THE CONTRACTOR MAY SUBSTITUTE MASONRY STRUCTURES FOR PRECAST STRUCTURES IF APPROVED BY THE SITE ENGINEER AND ALLOWED BY THE TOWN ENGINEER OR BY GOVERNING AUTHORITY.
- 31. All materials used for the installation and testing of the sanitary sewers and laterals within the Town of Burrillville
- 32. Disconnect Permits will be required for the removal of the existing sanitary sewer connections. Lines will be capped and sealed as close as possible to the main sanitary sewer line or manhole.
- 33. A connection permit will be required for the new sanitary sewer connection.
- 34. Manhole frames and covers shall meet Town of Burrillville specifications.

shall meet all Burrillville Wastewater Treatment Commission specifications.

#### POST CONSTRUCTION STORM WATER POLLUTION PLAN

RESPONSIBLE PARTIES AND STORMWATER MANAGEMENT SYSTEM OWNER: REBEL-UNION PARTNERS, LLC 93 NORTH MAIN STREET WEST HARTFORD, CT 06107

OF THE SYSTEM. UTILIZING A VACUUM TRUCK)

PHONE: 860-729-6812

THE FOLLOWING PROCEDURES WILL BE IMPLEMENTED CONTINUALLY BY THE OWNER:

- 1. PAVEMENT SWEEPING: PARKING LOTS AND DRIVES SHALL BE SWEPT A MINIMUM OF TWICE A YEAR (SPRING AND FALL)
- 2. CATCH BASINS: CATCH BASINS SHALL BE INSPECTED ON A REGULAR BASIS (AT LEAST TWICE PER YEAR) AND ANY SEDIMENT, OILS & FLOATABLES WILL BE REMOVED AS NECESSARY ( A MINIMUM OF ONCE A YEAR TO ENSURE FUNCTIONING
- 3. THE COLLECTION SYSTEM PIPES SHALL BE AT SIX-MONTH INTERVALS. REGULAR MAINTENANCE INCLUDES THE FOLLOWING
- -INSPECTION OF THE OUTLET TO ENSURE THEY ARE NOT BLOCKED -CHECKING THE OUTLETS FROM THE DRAINAGE SYSTEM IS CLEAR AND NOT ERODING. -REMOVING PAPER AND DEBRIS FROM INSIDE THE BASIN.
- 5. STORMWATER QUALITY BASIN SLOPES SHALL BE MOWED ONCE A YEAR. MORE FREQUENT MOWING WILL ELIMINATE NATIVE FORBS SEDGES FROM THE MEADOW COVER.
- 6. LANDSCAPING: LANDSCAPED AREAS WILL BE MAINTAINED. NORMAL LANDSCAPING MAINTENANCE WILL CONSIST OF PRUNING, MULCHING, PLANTING MOWING LAWNS, RAKING LEAVES, ECT.. USE OF FERTILIZERS AND PESTICIDE WILL BE CONTROLLED AND LIMITED TO MINIMAL AMOUNTS NECESSARY FOR HEALTHY LANDSCAPE MAINTENANCE. THE LAWN AREAS, ONCE ESTABLISHED, WILL BE MAINTAINED AT A TYPICAL HEIGHT OF 3 1/2". THIS WILL ALLOW THE THE GRASS TO BE MAINTAINED WITH A MINIMAL IMPACT FROM WEEDS AND/OR PEST. THE REAR (EASTERLY) SLOPE AREAS WILL BE MAINTAINED AS A MEADOW OR ALLOWED TO REVERT BACK TO WOODLANDS. PESTICIDE WILL ONLY BE USED AS A CONTROL METHOD WHEN A PROBLEM HAS BEEN IDENTIFIED AND OTHER NATURAL CONTROL METHODS ARE NOT SUCCESSFUL. ALL PESTICIDE APPLICATION SHALL BE BY LICENSED APPLICATORS, WHERE NECESSARY. TOPSOIL, BRUSH, LEAVES, CHIPPINGS, MULCH, EQUIPMENT, AND OTHER MATERIALS SHALL BE STORED OFF SITE.
- 7. MAINTAIN EXISTING NATIVE VEGETATION: EXISTING VEGETATION ALONG THE EASTERLY EDGE OF THE DEVELOPMENT, ADJACENT TO THE WETLANDS SHALL REMAIN IN ITS NATIVE CONDITIONS NO CLEARING, GRADING, STOCKPILING, STORAGE, OR DEVELOPMENT WILL OCCUR IN THESE AREAS WITHOUT PRIOR APPROVAL FROM THE APPROPRIATE AGENCIES.
- 8. TRASH COLLECTION: ALL TRASH WILL BE CONTAINED IN DUMPSTERS. ALL DUMPSTERS WILL BE EQUIPPED WITH COVERS.
- 9. OUTDOOR STORAGE: THERE WILL BE NO OUTDOOR OF HAZARDOUS CHEMICALS, FERTILIZER, PESTICIDES, OR HERBICIDE'S ANYWHERE AT THE FACILITY

ALL TRASH WILL BE COLLECTED ON A REGULAR BASIS AND DISPOSED OF LEGALLY OFF-SITE.

10. THE OWNER SHALL BE KEEP AN ON-SITE LOG OF STORMWATER MAINTENANCE MEASURES PERFORMED AND DATES THEY WERE IMPLEMENTED. THIS LOG BOOK SHALL BE AVAILABLE FOR THE TOWN OF BURRILLVILLE INSPECTION.

STORMWATER SYSTEM MAINTENANCE

The site will be maintained in a clean condition at all times by implementing good housekeeping measures Trash and surface debris will be removed from parking areas and stormwater structures. The site will be regularly cleaned of trash and debris. Stormwater structures (i.e., catch basins, stormwater quality basin, bio retention swales, underground infiltration systems, and level spreader, etc.) and outfalls will be cleaned of sediment and debris at least once a year, during the early month in the spring (once snow melt is complete) and at other times as necessary to prevent the off-site discharge of pollutants from the structures or outfalls. Special attention will be directed to the stormwater management basin identified on the site engineering drawings.

Stormwater Management Structures	Checked for
Catch Basins	Accumulated sediment & debris
Stormwater Infiltration Basin	Accumulated sediments, debris, evidence of erosion, etc.


#### SWEEPING SCHEDULE

All parking areas, sidewalks, loading areas and driveways will be swept as needed, with automatic air sweeping and vacuuming equipment

#### Yard Maintenance

- After irrigation, mowing is the most important maintenance operation. With good mowing practices, density, texture, color, root development, wear tolerance and other aspects of turf quality are enhanced, and a healthy turf minimizes the need for use of fertilizers and pesticides.
- When the turf is mowed too closely, it becomes less tolerant of environmental stresses, more disease prone, and more dependent upon a carefully implemented cultural program. The best approach then, is to use a high mowing height.
- Anytime that grass is in a weakened condition, the mowing height will be raised immediately.
- Growth rate and mowing height have the most influence on mowing frequency. As a rule of thumb, mowing should be done often enough that no more than 30 percent of the leaf is removed at any one mowing. This practice minimizes the effect of mowing on photosynthesis and helps maintain a high percentage of leaf surface, which is necessary for healthy root development.
- Varied mowing patterns on all surfaces encourage upright growth and reduce wheel or mower wear and compaction.
- Research has shown that returning grass clippings to the surface does not greatly increase thatch building up on turf that is otherwise properly managed. Clippings do have significant nutrient value and decompose rapidly thus returning some fertilizer and organic matter to the soil. They also help conserve moisture and insulate the soil

0



#### EROSION CONTROL NOTES

THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND THE WETLAND AREA FROM SURFACE RUNOFF AND EROSION. A CONSTRUCTION SEQUENCE IS PROVIDED TO PROVIDE SURFACE RUNOFF CONTROLS PRIOR TO THE PROJECT CONSTRUCTION BEGINNING.

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS SPRING 2024 WITH COMPLETION ANTICIPATED SUMMER 2024. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL CONSTRUCTION ACTIVITY.

CONTINGENCY EROSION PLAN

THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION. THE AGENTS OF THE DIRECTOR OF PLANNING & DEVELOPMENT, INLAND WETLANDS AGENCY AND/OR SITE ENGINEER SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

CONSTRUCTION SEQUENCE THE FOLLOWING CONSTRUCTION SEQUENCE IS RECOMMENDED:

- 1. CONTACT TOWN OF BURRILLVILLE AGENT AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO COMMENCEMENT OF ANY DEMOLITION, CONSTRUCTION OR REGULATED ACTIVITY ON the PROJECT. A PRE-CONSTRUCTION MEETING WITH LOCAL AND/OR STATE OFFICIALS NEEDS TO BE HELD PRIOR TO THE START OF CONSTRUCTION
- 2. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE TOWN OF BURRILLVILLE AGENT PRIOR TO THE START OF WORK ON THE SITE. INSTALL TREE PROTECTION AND PERIMETER SILT FENCE & HAY BALE SEDIMENT BARRIERS.
- 3. CONSTRUCT TRACKING PADS AT ENTRANCES AND WRAP FILTER FABRIC AROUND GRATE OF CATCH BASINS OR INSTALL SILT SACKS ON CATCH BASIN INLETS ON OFF SITE ROADS. INSTALL SILT FENCE AT PERIMETER OF PROPOSED SITE DISTURBANCE AND INSTALL ALL EROSION CONTROL MEASURES AND TREE PROTECTION INDICATED ON THESE PLANS. INSTALL SEDIMENT TRAPS AND INSTALL SEDIMENT BASINS IN REQUIRED AT LOW AREAS OF SITE OR AS ORDERED BY THE ENGINEER OR AS SHOWN ON THESE PLANS.
- 4. CLEAR AND GRUB SITE. STOCK PILE CHIPS. STRIP AND STOCKPILE TOPSOIL.
- 5. INSTALL ADDITIONAL SILT FENCE AS REQUIRED, CONSTRUCT TEMPORARY DIVERSION BERMS AND AND SEDIMENT TRAPS.
- 6. CONTINUE EARTHWORK. CONSTRUCT FILL SLOPE. INSTALL ADDITIONAL EROSION CONTROL AS REQUIRED. TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE GRADING.
- 7. CONSTRUCTION STAKING OF ALL BUILDING CORNERS, UTILITIES, ACCESS DRIVES, AND PARKING AREAS.
- 8. ROUGH GRADING.
- 9. CONSTRUCT STORM WATER QUALITY BASIN AND FINAL OUTLET.
- 10. INSTALLATION OF STORM DRAINAGE.
- 11. FOUNDATION CONSTRUCTION. BEGIN SUPERSTRUCTURE.
- 12. REMOVE SEDIMENT FROM BEHIND SILT FENCES, AND FROM SEDIMENTATION BASINS AS REQUIRED. REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL). INSPECTION OF EROSION CONTROL MEASURES SHALL BE ON A WEEKLY BASIS. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.
- 13. INSTALL SEPTIC, WELL AND ALL OTHER UTILITIES. COMPLETE STORM SEWERS.
- 14. INSTALL SITE LIGHTING, LOADING AREA AND TRASH ENCLOSURE.
- 15. FINISH GRADING AND CONSTRUCT PARKING AREA SUBGRADE.
- 16. CONSTRUCT SIDEWALKS.
- 17. PAVING OF PARKING AREAS AND DRIVEWAYS
- 18. FINAL GRADING OF SLOPE AREAS.
- 19. PLACE 4" TOPSOIL ON SLOPES AFTER FINAL GRADING IS COMPLETED. FERTILIZE SEED AND MULCH. SEED MIXTURE TO BE INSTALLED APRIL 11 TO JUNE 1 OR AUGUST 15 TO OCTOBER 1 USE EROSION CONTROL BLANKETS AS REQUIRED OR ORDERED FOR SLOPES GREATER THAN 3:1. FOR TEMPORARY STABILIZATION BEYOND SEEDING DATES USE ANNUAL RYE AT 4.0 LBS/1,000 S.F. FERTILIZE WITH 10-10-10 AT 1.0 LBS. OF NITROGEN PER 1,000 S.F. AND LIME AT 100 LBS/1,000 S.F. (MAX.).
- 20. LANDSCAPE ISLANDS AND PERIMETER AREAS, INSTALL SIGNING AND PAVEMENT MARKINGS.
- 21. UPON DIRECTION OF THE TOWN OF BURRILLVILLE AGENT, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED FOLLOWING STABILIZATION OF THE SITE.

OPERATION I - CLEARING AND GRUBBING

- 1. ALL SEDIMENTATION AND EROSION CONTROL MEASURES, INCLUDING THE CONSTRUCTION OF THE TEMPORARY SEDIMENT TRAPS AND ANTI-TRACKING PADS, WILL BE INSTALLED PRIOR TO THE START OF CLEARING AND GRUBBING AND DEMOLITION
- 2. FOLLOWING INSTALLATION OF ALL SEDIMENTATION AND EROSION CONTROL MEASURES, THE CONTRACTOR SHALL NOT PROCEED WITH OPERATION II UNTIL THE ENGINEER HAS INSPECTED AND APPROVED ALL INSTALLATIONS.
- 3. THE CONTRACTOR SHALL TAKE EXTREME CARE DURING OPERATION I, SO AS NOT TO DISTURB UNPROTECTED WETLAND AREAS OR SEDIMENTATION AND EROSION CONTROL STRUCTURES.

OPERATION II - ROUGH GRADING

- 1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE SITE PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.
- 2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, MULCHED WITH HAY, AND ENCLOSED BY A SILTATION FENCE.

OPERATION III - FILLING

- 1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL STRUCTURES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE ENGINEER AND AS SHOWN ON the PLAN.
- 2. ALL FILL MATERIAL ADJACENT TO ANY WETLAND AREAS SHALL BE GOOD QUALITY, WITH LESS THAN 5% FINES PASSING THROUGH A #200 SIEVE (BANK RUN), SHALL BE PLACED IN MAXIMUM ONE FOOT LIFTS, AND SHALL BE COMPACTED TO 95% MAX. DRY DENSITY MODIFIED PROCTOR OR AS SPECIFIED IN CONTRACT SPECIFICATIONS.
- 3. AS GENERAL GRADING OPERATIONS PROGRESS, THE TEMPORARY DIVERSION DITCHES SHALL BE RAISED OR LOWERED, AS NECESSARY, TO DIVERT SURFACE RUNOFF TO THE BASINS.
- OPERATION IV PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND BUILDING CONSTRUCTION.
- 1. STAKED SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF BUILDING EXCAVATIONS, DEWATERING PUMP DISCHARGES, AND UTILITY TRENCH MATERIAL STOCKPILES.

OPERATION V - FINAL GRADING AND PAVING

- 1. ALL INLET AND OUTLET PROTECTION SHALL BE PLACED AND MAINTAINED AS DISCUSSED IN OPERATION IV.
- 2. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND THE ROAD SHOULDER AND BANKS WILL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.
- 3. PAVEMENT BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES HAVE BEEN INSTALLED.
- 4. CONSTRUCT PAVEMENT, PLACE TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING.
- 5. REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE TOWN OR GOVERNING WETLAND AGENCY.

<u>SEQUENCE FOR INSTALLATION OF SOIL EROSION</u> & SEDIMENTATION CONTROL MEASURES

- 1. ERECT SILTATION FENCES, SEDIMENT TRAPS, DIVERSION DITCHES, AND ANTI-TRACKING PAD.
- 2. STRIP TOPSOIL AND STOCKPILE.

2. PERFORM FILLING ACTIVITIES.

- 3. PERFORM CLEARING AND GRUBBING ACTIVITIES, AND DEMOLITION.
- 4. STABILIZE STOCK PILE.

1. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.

2. ROUGH GRADING.

1. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.

PHASE 4 1. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.

- 2. CONSTRUCT DRAINAGE STRUCTURES. CONSTRUCT DIVERSION BERMS, RIP RAPPED LINED DITCHES AND SEDIMENTATION BASINS.
- 1. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 2. PERFORM FINAL GRADING AND PAVING.
- 1. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 2. RESPREAD TOPSOIL.
- 3. LIME, FERTILIZE, AND SEED.
- 4. MULCH.
- 5. FINAL COVER.

1. MAINTAIN SILTATION FENCES UNTIL COVER IS COMPLETELY STABILIZED

- 2. PERFORM FINAL INSPECTION.
- 3. REMOVE SILTATION FENCES, CLEAN, AND RESTORE ALL AREAS.

NSTALLATION OF SEDIMENTATION AND EROSION CONTROL MEASURES

- A. DIG A SIX INCH TRENCH ON THE UPHILL SIDE OF THE DESIGNATED FENCE LINE LOCATION.
- B. POSITION THE POST AT THE BACK OF THE TRENCH (DOWNHILL SIDE), AND HAMMER THE POST AT LEAST 1.5 FEET INTO THE GROUND.
- C. LAY THE BOTTOM SIX INCHES OF THE FABRIC IN THE TRENCH TO PREVENT UNDERMINING BY STORM WATER RUN-OFF.
- D. BACKFILL THE TRENCH AND COMPACT.

OPERATION AND MAINTENANCE OF SEDIMENTATION AND EROSION CONTROL MEASURES

- . SILTATION FENCE A. ALL SILTATION FENCES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH the PLAN.
- B. SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED A HEIGHT OF ONE FOOT.
- A. CONTRACTOR TO KEEP WEEKLY CHECKLIST LOGS FOR INSPECTIONS OF ALL SEDIMENT AND EROSION CONTROL DEVICES AND HAVE THEM READILY AVAILABLE ON-SITE AT ALL TIMES FOR INSPECTION BY DEEP, LOCAL AUTHORITIES OR ENGINEER.
- B. ALL PONDS SHALL BE INSPECTED FOLLOWING EACH RAINFALL. REPAIR OF SLOPES SHALL BE PROMPTLY MADE AS NEEDED.
- C. SEDIMENT DEPOSITS SHALL BE REMOVED FROM PONDS WHEN THEY EXCEED A HEIGHT OF ONE FOOT.
- D. SEDIMENT SHALL BE DISPOSED OF ON-SITE OR AS DIRECTED BY THE ENGINEER AND LOCAL GOVERNING OFFICIALS.
- SILTATION FENCE WILL BE INSTALLED AT ALL CULVERT OUTLETS AND ALONG THE TOE OF ALL CRITICAL CUT AND FILL
- 2. CATCH BASINS WILL BE PROTECTED WITH SILT SACKS OR HAY BALES THROUGHOUT THE CONSTRUCTION PERIOD AND UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.
- 4. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO CONSTRUCTION WHENEVER POSSIBLE.
- 5. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
- 6. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF NECESSARY OR REQUIRED.
- 7. SEDIMENT REMOVED FROM CONTROL STRUCTURES WILL BE DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THE PLAN.
- 8. REBEL-UNION PARTNERS, LLC IS THE PERMITEE RESPONSIBLE FOR IMPLEMENTING the EROSION AND SEDIMENT CONTROL PLAN. the RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES. INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, NOTIFICATION OF THE BURRILLVILLE WETLANDS ENFORCEMENT OFFICER OR GOVERNING AUTHORITY OF THE TRANSFER OF the RESPONSIBILITY AND FOR CONVEYING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.

- EROSION AND SEDIMENT CONTROL PLAN SEDIMENT AND EROSION CONTROL NOTES

  1. THE DRAWING IS ONLY INTENDED TO DESCRIBE THE SEDIMENT AND EROSION CONTROL TREATMENT FOR the SITE. SEE SEDIMENT AND EROSION CONTROL DETAILS AND CONSTRUCTION SEQUENCE. REFER TO SITE PLAN FOR GENERAL INFORMATION AND OTHER PLANS FOR APPROPRIATE INFORMATION.
- 2. REBEL-UNION PARTNERS, LLC IS THE PERMITEE RESPONSIBLE FOR IMPLEMENTING the SEDIMENT AND EROSION CONTROL PLAN. THE RESPONSIBILITY INCLUDES THE PROPER INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED WITH CONSTRUCTION ON THE SITE OF THE REQUIREMENTS AND OBJECTIVES OF the PLAN, INFORMING THE GOVERNING AUTHORITY OR INLAND WETLANDS AGENCY OF ANY TRANSFER OF the RESPONSIBILITY, AND FOR CONVEYING A COPY OF THE SEDIMENT & EROSION CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.
- 3. THE CONTRACTOR SHALL CONSTRUCT ALL SEDIMENT AND EROSION CONTROLS IN ACCORDANCE WITH THE RHODE ISLAND GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL, LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS, AND AS DIRECTED BY THE TOWN OF BURRILLVILLE. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON-SITE FOR REFERENCE DURING CONSTRUCTION.
- 4. ADDITIONAL AND/OR ALTERNATIVE SEDIMENT AND EROSION CONTROL MEASURES MAY BE INSTALLED DURING THE CONSTRUCTION PERIOD IF FOUND NECESSARY BY THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICIALS, OR ANY GOVERNING AGENCY. THE CONTRACTOR SHALL CONTACT THE OWNER AND APPROPRIATE GOVERNING AGENCIES FOR APPROVAL IF ALTERNATIVE CONTROLS OTHER THAN THOSE SHOWN ON THE PLANS ARE PROPOSED.

Routine Inspections

The permittee shall routinely inspect the site for compliance with the general permit and the Plan for the site until a Notice of Termination has been submitted. Inspection procedures for these routine inspections shall be addressed and implemented in the following manner:

(i) The permittee shall maintain a rain gauge on—site to document rainfall amounts. At least once a week and within 24 hours of the end of a storm that generates a discharge, a qualified inspector (provided by the permittee), as defined in the "Definitions" section (Section 2) of the general permit, shall inspect, at a minimum, the following: disturbed areas of the construction activity that have not been finally stabilized; all erosion and sedimentation control measures; all structural control measures; soil stockpile areas; washout areas and locations where vehicles enter or exit the site. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and impacts to the receiving waters. Locations where vehicles enter or exit the site shall also be inspected for evidence of off—site sediment tracking. For storms that end on a weekend, holiday or other time after which normal working hours will not commence within 24 hours, an inspection is required within 24 hours only for storms that equal or exceed 0.5 inches. For storms of less than 0.5 inches, an inspection shall occur immediately upon the start of the subsequent normal working hours. Where sites have been temporarily or finally stabilized, such inspection shall be conducted at least once every month for three months.

(ii) The qualified inspector(s) shall evaluate the effectiveness of erosion and sediment controls, structural controls, stabilization practices, and any other controls implemented to prevent pollution and determine if it is necessary to install, maintain, or repair such controls and/or practices to improve the quality of stormwater discharge(s).

(iii) A report shall be prepared and retained as part of the Plan. the report shall summarize: the scope of the inspection; name(s) and qualifications of personnel making the inspection; the date(s) of the inspection; weather conditions including precipitation information; major observations relating to erosion and sediment controls and the implementation of the Plan; a description of the stormwater discharge(s) from the site; and any water quality monitoring performed during the inspection. The report shall be signed by the permittee or his/her authorized representative in accordance with the "Certification of Documents" section (subsection 5(i)) of the general permit. The report shall include a statement that, in the judgment of the qualified inspector(s) conducting the site inspection, the site is either in compliance or out of compliance with the terms and conditions of the Plan and permit. If the site inspection indicates that the site is out of compliance, the inspection report shall include a summary of the remedial actions required to bring the site back into compliance. Non—engineered corrective actions (as identified in the Guidelines) shall be implemented on site within 24 hours and incorporated into a revised Plan within three (3) calendar days of the date of inspection unless another schedule is specified in the Guidelines. Engineered corrective actions (as identified in the Guidelines) shall be implemented on site within seven (7) days and incorporated into a revised Plan within ten (10) days of the date of inspection, unless another schedule is specified in the Guidelines or is approved by the commissioner. During the period in which any corrective actions are being developed and have not yet been fully implemented, interim measures shall be implemented to minimize the potential for the discharge of pollutants from the site.

(iv) Inspectors from the DEEP and the appropriate District may inspect the site for compliance with the general permit at any time construction activities are ongoing and upon completion of construction activities to verify the final stabilization of the site and/or the installation of post-construction stormwater management measures pursuant to Section 6(a).

(v) Additional inspections, reports and documentation may also be required to comply with the "Monitoring Requirements" section (Section 5(c))

- 6. THE CONTRACTOR SHALL KEEP A SUPPLY OF EROSION CONTROL MATERIAL (SILT FENCE, JUTE MESH, ETC.) ON-SITE FOR MAINTENANCE AND EMERGENCY REPAIRS.
- 7. PROTECT EXISTING TREES THAT ARE TO BE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE, ORANGE SAFETY FENCE, OR EQUIVALENT FENCING. ANY LIMB TRIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN THAT AREA; FENCING SHALL BE MAINTAINED AND REPAIRED DURING CONSTRUCTION.
- 8. INSTALL PERIMETER SEDIMENT CONTROLS PRIOR TO CLEARING OR CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED WITHIN THE LIMIT OF DISTURBANCE, WHICH SHALL BE MARKED WITH SILT FENCE, SAFETY FENCE, RIBBONS, OR OTHER MEANS PRIOR TO CLEARING. CONSTRUCTION ACTIVITY SHALL REMAIN ON THE UPHILL SIDE OF THE SILT FENCE UNLESS WORK IS SPECIFICALLY CALLED FOR ON THE DOWNHILL SIDE OF THE FENCE.
- 9. ANTI-TRACKING PADS SHALL BE INSTALLED AT START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION. THE LOCATION OF THE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.
- 10. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE SILT FENCE AROUND THE LIMIT OF PILE. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE THAN 2 MONTHS.
- 11. SEDIMENTATION BASINS SHALL PROVIDE 134 CUBIC YARDS OF SEDIMENT STORAGE PER DISTURBED ACRE CONTRIBUTING TO THE BASIN. PROVIDE BASIN VOLUMES FOR ALL DISTURBANCE ON SITE.
- 12. COMPLY WITH REQUIREMENTS OF CGS SECTION 22A, 430B FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES AND WITH DEEP RECORD KEEPING AND INSPECTION REQUIREMENTS.
- 13. MINIMIZE LAND DISTURBANCES. SEED AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2 WEEK MAXIMUM UNSTABILIZED PERIOD) USING PERENNIAL RYEGRASS AT 40 LBS PER ACRE. MULCH ALL CUT AND FILL SLOPES AND SWALES WITH LOOSE HAY AT A RATE OF 2 TONS PER ACRE. IF NECESSARY, REPLACE LOOSE HAY ON SLOPES WITH EROSION CONTROL BLANKETS OR JUTE CLOTH. MODERATELY GRADED AREAS, ISLANDS, AND TEMPORARY CONSTRUCTION STAGING AREAS MAY BE HYDROSEEDED WITH TACKIFIER.
- 14. SILT FENCE AND OTHER SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH DRAWINGS AND MANUFACTURER'S RECOMMENDATIONS PRIOR TO WORK IN ANY UPLAND AREAS.
- 15. EXCAVATED MATERIAL FROM TEMPORARY SEDIMENT TRAPS MUST BE STOCKPILED ON UPHILL SIDE OF SILT FENCE.
- 16. INSTALL SILT FENCE ACCORDING TO MANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO GROUND. SILT FENCE SHALL BE MIRAFI ENVIROFENCE, AMOCO SILT STOP OR EQUIVALENT APPROVED BY SITE ENGINEER. FILTER FABRIC USED SHALL BE MIRAFI 100X OR EQUIVALENT.
- 17. INSTALL TEMPORARY DIVERSION DITCHES, PLUNGE POOLS, SEDIMENT BASINS, SEDIMENT TRAPS AND DEWATERING PITS AS SHOWN AND AS NECESSARY DURING VARIOUS PHASES OF CONSTRUCTION TO CONTROL RUNOFF UNTIL UPHILL AREAS ARE STABILIZED. LOCATION OF TEMPORARY SEDIMENT BASINS WILL REQUIRE REVIEW AND APPROVAL BY THE ENGINEER AND GOVERNING OFFICIAL.
- OR GRASS FILTERS WITHIN THE APPROVED LIMIT OF DISTURBANCE. DISCHARGE TO STORM SEWERS OR SURFACE WATERS FROM SEDIMENT CONTROLS SHALL BE CLEAR. 19. BLOCK THE OPEN UPSTREAM ENDS OF DETENTION PIPE SYSTEM OUTLET CONTROL ORIFICE UNTIL SITE IS STABILIZED AND BLOCK END OF STORM SEWERS IN EXPOSED TRENCHES WITH BOARDS AND SANDBAGS AT THE END OF EACH WORKING DAY


18. DIRECT ALL DEWATERING PUMP DISCHARGE TO A SEDIMENT CONTROL DEVICE SUCH AS TEMPORARY PITS, SEDIMENT BASINS


- WHEN RAIN IS EXPECTED. 20. SWEEP AFFECTED PORTIONS OF OFF SITE ROADS ONE OR MORE TIMES A DAY (OR LESS FREQUENTLY IF TRACKING IS NOT A PROBLEM) DURING CONSTRUCTION. OTHER DUST CONTROL MEASURES TO BE USED AS NECESSARY INCLUDES WATERING
- DOWN DISTURBED AREAS, USING CALCIUM CHLORIDE, AND COVERING LOADS ON DUMP TRUCKS. 21. PERIODICALLY CHECK ACCUMULATED SEDIMENT LEVELS IN THE SEDIMENT TRAPS DURING CONSTRUCTION AND CLEAN ACCUMULATED SILT WHEN NECESSARY OR WHEN ONE FOOT OF SEDIMENT HAS ACCUMULATED. CLEAN ACCUMULATED SEDIMENT FROM CATCH BASIN SUMPS AS NECESSARY. REMOVE ACCUMULATED SEDIMENT FROM BEHIND SILT FENCE WHEN LEVEL REACHES
- 22. MAINTAIN ALL PERMANENT AND TEMPORARY SEDIMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD. UPON COMPLETION OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDIMENT CONTROLS WHEN AUTHORIZED BY LOCAL GOVERNING AUTHORITY.
- 23. THE PARTY RESPONSIBLE FOR THE EROSION AND SEDIMENT CONTROL MEASURES IS: REBEL-UNION PARTNERS, LLC ATTN: MARK D'ADABBO 93 NORTH MAIN STREET
- 24. IF WIND EROSION OCCURS, THEN GROUND SHALL BE COVERED WITH CALCIUM CHLORIDE OR WATER TRACK APPLICATIONS AS REQUIRED TO CORRECT THE PROBLEM.


HALF THE HEIGHT OF THE FENCE. DISPOSE OF SEDIMENT LEGALLY EITHER ON SITE IN NON-WETLANDS AREAS..


Ø 0
































































































SCALE: AS SHOWN

DATE: DEC. 28, 2023

DRAWN BY: JMP

JOB No.: 3470

ACAD FILE: 3470–DET

SHEET:

REVISIONS:

MARCH 02, 2024 PER PEER REVEW AND PLANNER COMMENTS


PEARSON & CASSIDY
EERS & LAND SURVEYORS
AIN STREET, UNIT #1A
ILL, CONNECTICUT 06416


HALLISEY, PEARS


CIVIL ENGINEERS & LA

630 MAIN STREET,

PREPARED FOR
REBEL-UNION PARTNERS, LLC
PROPERTY LOCATED AT
BRONCOS HIGHWAY (RT. #102)











### TRASH ENCLOSURE PLAN WITH CHAIN LINK FENCE

N.T.S.













PREPARED FOR
PREPARED FOR
REBEL-UNION PARTNERS, LLC
PROPERTY LOCATED AT
BRONCOS HIGHWAY (RT. #102
BURRILLVILLE, RHODE ISLAI





SUGAR MAPLE OWERING DOGWOOD

W W

6'-7' HGT. |5"-2" CALIP.

SCALE: 1"=20'

JOB No.: 3470

S SUFFICIENT TO COMPLETE THE LIST. IN THE EVENT OF A AND THOSE REQUIRED BY THE

DRAWN BY: JMP DATE: DEC. 28, 2023 ACAD FILE: 3470-ZI-S S

REVISIONS: MARCH 02, 2024 PER PEER REVIEW AND PLANNER COMMENTS

LE FOR ANY DAMAGE VEGETATION AND SHALL REPLACE OR ... HIS OWN EXPENSE. THE CONTRACTOR SHALL CONTACT "CAI CONSTRUCTION. **D** WITH SHREDDED

9 AREAS SHALL BE HAVE CONTINUOUS BEDS OF HAVE A MINIMUM TOPSOIL BED OF 6". ALL UTILITIES IN THE FILED. WERE PLANT ACTOR SHALL NOTIFY THE LANDSCAPE INSTALLATION.

L EXISTING RILL, GULL OR CHANNEL EROSION SHALL BE FILLED WITH APPROPRIATE BACKFILL KIAL, FINE RAKED, SCARIFIED AND STABILIZED WITH APPROPRIATE VEGETATIVE MATERIAL OR APPROPRIATE SEDIMENTATION AND EROSION CONTROL MEASURES.

14. PLANTINGS INSTALLED IN THE DRY SUMMER MONTHS AND / OR LAWN SPRING OR FALL PERIODS, IF ALLOWED BY OWNER, WILL REQUIRE AGGREPROGRAMS AT THE CONTRACTOR'S EXPENSE, UNLESS DIRECTED BY THE C OIL, MULCH, AND SHOULD BE COMPLETED IS ALL DAMAGED IG FROM LANDSCAPING OWNER.

ONTRACTOR SHALL SURVEY, LOCATE, AND PROTECT ALL TREES WITHIN AREAS SHOWN AS 3TING VEGETATION TO REMAIN" WITHIN THE DEVELOPMENT ENVELOPE FOR REVIEW BY 2SCAPE ARCHITECT OR CIVIL ENGINEER PRIOR TO CLEARING OPERATIONS.

7

1 TONS/ACRE (90 ) (7.5 |bs./1000 sc 1bs./1*000* ;q. ft.)

@40LBS.

@10L\$5./ACRE @10L\$5./ACRE @5./ACRE 45LBS./ACRE

- & SEED FROM EROSION AFTER FINAL GRADING

and MAINTENANCE שַ

OR MUDDY.

SITE LANDSCAPING PLAN PREPARED FOR

**REBEL-UNION PARTNERS, LLC PROPERTY LOCATED AT BRONCOS HIGHWAY (RT. #102) BURRILLVILLE, RHODE ISLAND** 

## **HALLISEY, PEARSON & CASSIDY**

CIVIL ENGINEERS & LAND SURVEYORS
630 MAIN STREET, UNIT #1A
CROMWELL, CONNECTICUT 06416
PHONE: (860)-529-6812, FAX: (860)-721-7709

